

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21197-00-00
Spot: SWNWSNW Sec/Twnshp/Rge: 2-10S-26W
3432 feet from S Section Line, 1584 feet from W Section Line
Lease Name: WERTH Well #: 1
County: SHERIDAN Total Vertical Depth: 4100 feet

Operator License No.: 34117
Op Name: ETERNITY EXPLORATION, LLC
Address: 901 LAVACA TRAIL
COLLEYVILLE, TX 76034

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207		

133.25

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/05/2008 1:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 05/05/2008 2:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 2249' w/25 sxs.
2nd. Plug at 1017' w/100 sxs.
3rd. Plug at 257' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

INVOICED
DATE 5-20-08
INV. NO. 2008061740

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 12 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: S.O.S. CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

MAY 07 2008

PKY