

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20407-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 1-11S-25W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HOBBS DEAN Well #: 1  
County: TREGO Total Vertical Depth: 4015 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4015	0	125 SX
SURF	8.625	208	0	125 SX

130.49

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/01/2008 1:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY MORRIS Company: GLM COMPANY Phone: (785) 483-1307

Proposed Plugging Method: Ordered 415 sxs 60/40 pozmix - 4% gel - 400# hulls - 8 sxs gel. Perf at 2050' - 1150' - 220'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2008 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing in to 3700' - pumped 8 sxs gel - 50 sxs cement with 100# hulls.  
Pulled tubing to 2250' - pumped 215 sxs - ran out of cement - had little returns and drilling mud.  
Pulled tubing out - waited until 05/06/2008.  
05/06/2008 - Wireline found cement at 480'.  
Ran tubing to 480' - pumped 30 sxs cement - circulated the 4 1/2" with cement.  
Pulled tubing out - tied onto 4 1/2" - pumped 40 sxs cement.  
Circulated out 8 5/8" - shut in 8 5/8".  
Squeezed 4 1/2" with 80 sxs cement and 300# hulls.  
Max. P.S.I. 300#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3944	3982		
3880	3899		
3829	3844		

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 12 2008  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #1966 AND #1951.

DATE 5/20/08  
INV. NO. 2008061742

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

CM

MAY 07 2008

[Handwritten mark]

14

COPY TO 10/10/77

HELBERG OIL CO.  
BOX 32, MORLAND, KS.

#1 DEAN HOBBS

1-11-25W  
SW SW SE

CONTR CO. TOOLS

CTY TREGO

GEOL DICK GREEN

FIELD TIDBALL EXT (1/8 N)

E 2403 KB CM 4/8/77

CARD  
ISSUED

6/9/77

IP P 150 BOPD, NW  
LKC 3883-89

+	+
+	+

API 15-195-20,407

LOG	TOPS	DEPTH	DATUM
HEEB		3705	-1302
TOR		3727	-1324
LKC		3743	-1340
EAC		3981	-1578
RTD		4015	-1612

8-5/8" 208, 4 1/2" 4013/175sx  
 DST (1) 3761-3805/30-30-30-30, 70'  
 SOCM, SIP 781-644#, FP 43-43#, 53-53#  
 DST (2) 3865-3920 (LKC)/30-30-30-30,  
 1060'GIP, 900'CO, SIP 409-409#, FP 183-290#, 377-409#  
 DST (3) 3913-3960 (LKC)/30-30-30-30,  
 GTS/30", 2800'FO, SIP 1225-1194#, FP 398-718#, 834-961#  
 MICT - CO & PF 3883-89, SWB 14BOPH, NAT, A 1000, SWB LD & SWB 30BOPH, NW, POP, P 150BOPD, NW

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS