

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25183-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 10-17S-13W  
1000 feet from S Section Line, 1100 feet from E Section Line  
Lease Name: KOESTER BROTHERS Well #: 1-10  
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1560 BROADWAY STE 2100  
DENVER, CO 80202

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 395        |             |          |

111.48

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2008 12:00 PM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: KRIER Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE  
Date/Time Plugging Completed: 05/05/2008 3:15 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 3320' w/25 sxs.  
2nd. Plug at 800' w/25 sxs.  
3rd. Plug at 445' w/90 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

**INVOICED**  
DATE 5-20-08  
INV. NO. 2008061749

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 12 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Basye  
(TECHNICIAN)

CM

Form CP-2/3

MAY 06 2008

PKT