

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: F. G. Holl Company, L.L.C.

Address: 9431 E Central, Suite 100, Wichita, KS 67206

Phone: (316) 684-8481 Operator License #: 5056

Type of Well: D&A Oil KCCPRT Per CP 213 Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 04/02/2008 (Date)

by: Doug Louis (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-141-20,364-0000

Lease Name: Kendig

Well Number: 1-32

Spot Location (QQQQ): C - E2 - NW - NE

660 Feet from  North /  South Section Line

1650 Feet from  East /  West Section Line

Sec. 32 Twp. 9 S. R. 12  East  West

County: Osborne

Date Well Completed: 12/08/2006

Plugging Commenced: 4-2-08

Plugging Completed: 4-7-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	240	
				4 1/2	3400	1600

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3175', bailed 4 sacks cement, ripped casing at 2010', worked pipe, ripped casing at 1840', worked pipe, ripped casing at 1600', worked pipe free, pulled to 1550', pumped 100 sacks, 300# hulls, pulled to 1100', pumped 35 sacks, 100# hulls, pulled to 800', pumped 35 sacks, 100# hulls, pulled to 200', circulated with 65 sacks to surface, pulled rest of casing.

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 29 2008

CONSERVATION DIVISION  
WICHITA, KS

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526


Name of Party Responsible for Plugging Fees: F. G. Holl Company, L.L.C.

State of Kansas County, Sedgwick, ss.

Adam T. Thorne (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 9431 E. Central, Wichita Ks.



Notary Public - State of Kansas  
BETTY H. SPOTSWOOD

My Appointment Expires 4/30/2010

SUBSCRIBED and SWORN TO before me this 28 day of April, 2008

Betty H. Spotswood My Commission Expires: 4/30/2010

Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten initials]*