

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-019-19497-00-00

API NUMBER None

LEASE NAME Alford

WELL NUMBER 34

891 Ft. from S Section Line

4785 Ft. from E Section Line

SEC. 32 TWP. 33 RGE. 12 (E) or (W)

COUNTY Chautauque

Date Well Completed 1945

Plugging Commenced 11-14-07

Plugging Completed 11-15-07

KCC
 PRT
 Per
 plat
 map

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR John A Elmore

ADDRESS 776 Hwy 99 Sedan Kansas 67361

PHONE (620) 725-5538 OPERATORS LICENSE NO. 5970

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-14-07 (date)

by KCC Chautauque office (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? None

Producing Formation Peru Depth to Top 1040 Bottom 1075 T.D. 1111'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Peru Sand	37'	901	Surf	6 5/8	901	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:
Pulled Tubin + Packer Out Ran 1" Tubin To 980' Pumped 20 BBL Tool Water
Spotted 25 Sks Cement Pulled 1" up To 700' Spotted 20 Sks Cement Pulled
1" out Perforated Casing At 350' Ran 1" To 350' Cemented Inside
+ Out Side Casing 350' To Surf With 125 Sks Cement

Name of Plugging Contractor Elmore's Inc License No. 32884

Address PO Box 87 Sedan Kansas 67361

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John A Elmore

STATE OF Kansas COUNTY OF Chautauque, ss.

John A Elmore (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) John A Elmore

(Address) _____

SUBSCRIBED AND SWORN TO before me this 7th day of Feb, 192008

Jennifer Monday CSR FNS
 Notary Public

My Commission Expires:



RECEIVED
 KANSAS CORPORATION COMMISSION

FEB 14 2008

CONSERVATION DIVISION
 WICHITA