

15-173-19064-00-01


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick County. Sec. 11 Twp. 26 Rge. 2 (E) W1

Location as "NE/CNW&SW" or footage from lines SE SW SW
Lease Owner Sohio Petroleum Company
Lease Name Erdwein Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 19 33
Application for plugging filed February 8, 19 55
Application for plugging approved March 3, 19 55
Plugging commenced March 23, 19 55
Plugging completed March 25, 19 55
Reason for abandonment of well or producing formation Uneconomical



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production August 18, 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2888 Feet
Show depth and thickness of all water, oil and gas formations. 3308 ANG

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	2855'	2202'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

2888' to 2812' - 155 gallons sand and 8 sacks cement
2812' to 190' - Heavy mud
190' to 185' - Rock bridge
185' to 30' - 20 sacks cement and mud
30' to 20' - Rock Bridge
20' to Cellar - 10 sacks cement


RECEIVED
STATE CORPORATION COMMISSION
MAR 7 2 1955
3-30-55
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
J. N. Bond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. N. Bond
(Address) _____

SUBSCRIBED AND SWORN to before me this 29th day of March, 1955
Benedict B. Brown
Notary Public.



PLUGGING
FILE SEC 11 T 26 R 2E
BOOK PAGE 101 LINE 1

Casing Record:
 15 1/2" - 205' Left In
 12 1/2" - 1392' Pulled
 10" - 2250' Pulled
 8 1/4" - 2855' Left In

Farm - Erdwein
 Company - A. Aylward
 Commenced 2-3-33 Comp. 2-28-33
 Elevation 1372'

Location SE Corner W 1/2 SW 1/4
 of 11-26-2E, Sedgwick Co.
 Well #1
 Initial Production, 625 Bbls. Oil & 125
 Bbls. water in 18 hrs.

Formation	Depth	Formation	Depth	Formation	Depth
Cellar	8	Slate	1100	Lime	2290
Yellow Clay	20	Lime	1105	Slate	2305
Yellow Clay	60	Slate	1110	Lime	2335
H.F.W. at 60-65'		Lime	1125	Slate	2355
Shale Sandy	65	Slate Dark	1145	Slate & Shells	2400
Slate Blue	80	Lime	1150	Lime	2425
Lime	90	Slate Dark	1160	Slate	2440
Lime	95	Lime	1165	5 B.W. at 2465-75'	
Slate Blue	110	Slate	1170	Lime	2570
Lime	120	Lime	1180	Slate	2630
Slate	165	Slate	1185	Lime	2635
Lime	175	Lime	1195	Slate	2640
Shale Sandy	185	Slate	1205	Lime	2645
Slate	210	Lime	1220	Slate	2650
15 1/2" set at 205'		Slate	1235	Hole Caving	
Slate Blue	220	Lime	1250	Slate	2705
Lime	255	Slate	1265	Lime	2765
Slate Blue	265	Lime	1275	Slate	2770
Red Rock	280	Slate	1350	Lime	2775
Lime	320	Lime	1355	Slate	2780
Slate	325	Slate	1365	Lime	2795
Lime	420	H.F.W. at 1360-90'		Slate	2808
1/2 B.W.P.H. at 390'		Lime Sandy	1390	Lime	2816
Slate Blue	460	12 1/2" Casing at 1392'		Slate	2825
Lime	465	Lime	1398	Var.Col. Shale	2847
Slate	475	Slate	1402	Sandy Lime	2850
Lime	500	Lime	1410	Chat 8 1/4" set 2855'	2855
Slate	505	Lime	1415	Lime Broken	2869
Lime	525	Slate	1420	Chat	2876
Red Rock	530	1/2 B.W. from 1420-35'		Chat	2910
Lime	550	Lime	1435	Lime	2937
Slate	560	Slate	1450	Lime Sandy	2950
Lime	590	Lime	1475	Lime	3115
Slate	595	Slate	1495	Shale	3164
Lime	620	Lime	1535	Oil Sand	3166
Slate	625	Slate	1560	I hereby certify that this is a true and correct log of the above described well, to the best of my knowledge.	
Lime	635	Lime	1585	Contractor	
Slate	640	Slate	1595	Subscribed and sworn to before me this _____ day of _____, 1933, at Wichita, Kansas.	
Lime	715	Lime	1620	Notary Public	
Slate	725	Slate	1650	My Commission expires January 19, 1935.	
Slate Dark	730	Lime	1665	Set 6-5/8" at 3075'	
Lime	745	Slate	1675	Reduced hole to 5-3/16" @ 3150'	
Slate	750	Lime	1690	<div style="border: 2px solid black; padding: 5px; width: fit-content; margin: 0 auto;"> <p style="text-align: center; margin: 0;">PLUGGING</p> <p style="text-align: center; margin: 0;">PRK SEC 11 T 26 R 2E</p> <p style="text-align: center; margin: 0;">BOOK PAGE 101 LINE 1</p> </div>	
Lime	755	Slate	1700		
Slate	765	Lime	1730		
Lime	795	Slate Shells	1760		
Slate	800	Lime	1805		
Lime	835	Slate	1810		
Slate	840	Lime	1845		
Lime	855	Slate	1850		
Slate	865	Lime	1870		
Lime	870	Slate	1875		
Slate	890	Lime	1895		
Lime	900	Slate	1930		
Slate	920	Lime	1935		
Lime	930	Slate	1965		
Red Rock	940	Lime	1975		
Slate	945	Slate	2050		
Lime	960	Lime	2070		
Red Rock	965	Slate	2075		
Lime	970	Red Rock	2080		
Slate	1000	Slate	2095		
Lime Sandy	1015	Slate	2100		
6 B.W. at 1000-15'		Lime	2130		
Red Rock	1020	Slate	2190		
Slate	1060	Lime	2200		
Lime	1070	Slate	2205		
Slate	1075	Lime	2240		
Red Rock	1080	Slate	2245		
		Set 10" at 2250'			

ERDWEIN WELL #1

Company: The Aylward Production Company
Contractor: The Aylward Production Company

SE Corner of the W $\frac{1}{2}$ of the SW $\frac{1}{4}$ of
Sec. 11-26S-2E, Sedgwick Co., Kansas

Commenced: December 19, 1941
Completed: January 26, 1942

Elevation: 1,372'
Potential:

D E E P E N I N G R E C O R D

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Original Depth	3166		
Lime	3166	3240	
Sand	3240	3257	
Lime	3257	3268	
Slate	3268	3271	
Slate Sandy	3271	3275	
Slate	3275	3281	
Green Shale	3281	3286	
Shale Sandy	3286	3298	Set 5-3/16" @ 3282' and cemented
Sand	3298	3308 $\frac{1}{2}$	Show oil 3298' w/50 sax Swabbing and testing Filled up 350' in 4 hrs.

Plugged back with cement from TD of 3308 $\frac{1}{2}$ ' to 2874'.
Pulled 5 $\frac{1}{2}$ " casing from 2891'. SLM. Present PBTD 2874'.

RECEIVED
COMMISSION
MAR 27 1955
CONSERVATION DIVISION
Wichita, Kansas