

API NUMBER 15-173-20,332-00
 LEASE NAME Burne
 WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

SE Ft. from S Section Line
SE Ft. from E Section Line
 SEC. 11 TWP. 26S RGE. 2E (E) or (W)
 COUNTY Sedgwick
 Date Well Completed 1-25-81
 Plugging Commenced 1/86
 Plugging Completed 12-26-81

LEASE OPERATOR Marshall Oil Co
 ADDRESS Box 306 Fureka Ks
 PHONE# (316) 523-7595 OPERATORS LICENSE NO. 5409
 Character of Well 3WD
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 3197 Bottom 3214 T.D. 3308 ^{PB}

Show depth and thickness of all water, oil and gas formations. T.D. 3330 ^{K&B} _{KCC}

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				<u>8 7/8</u>	<u>205</u>	<u>0</u>
				<u>4 1/2</u>	<u>3308</u>	<u>1900</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand 2900' Dumped 55 sac cement w/ dump trailer.
Set well down shot & pulled pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Grossel Oil Field Serv Inc License No. 3004

Address Box 607 Burton Ks 67020

STATE OF Ks COUNTY OF Harvey, ss. 1-6-87

Ed Grossel (Employee of Operator) dan (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well ^{CONSERVATION} filed that the same are true and correct, so help me God.

(Signature) Ed Grossel

(Address) Box 607 Burton Ks 67020

SUBSCRIBED AND SWORN TO before me this 5th day of January, 1987



Mary H. Klein
 Notary Public

My Commission Expires: March 15, 1989

Contractor: E.D.C.O. Drilling Company
Rotary: Surface to 3330' RTD
Date Spudded: January 20, 1981
Date Completed: January 25, 1981

GEOLOGICAL DATA:

10' samples saved from 2400' to 3330' RTD.

Recorded one (1) foot drilling time from 2200' to 3330' RTD.

Logs: None

Elevation: 1367' KB

Formation Tops: (All measurements from KB)

	<u>Sample</u>	<u>Datum</u>
Kansas City	2395	-1028
Base Kansas City	2564	-1197
Altamont	2631	-1264
Ft. Scott	2706	-1339
Cherokee	2736	-1369
Mississippi	2861	-1494
Kinderhook	3145	-1778
Hunton	3195	-1828
Viola	3240	-1873
Simpson SS	3280	-1913
RTD	3330	-1963

MAJOR ZONES OF INTEREST:

Mississippi: 2861' - 2876'

Chert, white and yellow, sharp, some white tripolitic, scattered fluorescence, no show of free oil.

Hunton: 3195' - 3211'

Dolomite, fine crystalline sucrosic with fair to good inter-crystalline porosity and a show of free oil, light gold scattered fluorescence, some cream, sharp vitreous chert. At the top, there were a very few clusters of sandstone, possibly Misner, with very good porosity and a show of free oil.

RECEIVED
STATE CORPORATION
CONS. DIV. WICHITA, KS

SEP 1 1981