

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-173-20260-00-00
API NUMBER 10-9-88

LEASE NAME ERDWEIN

WELL NUMBER #1

SPOT LOCATION SE-SW-SW

SEC. 11 TWP. 26 RGE. 2 (NE) or (N)

COUNTY Sg.

Date Well Completed 10-9-88

Plugging Commenced 3-18-88

Plugging Completed 3-24-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Midco Energy Inc

ADDRESS P.O. Box 781025

PHONE (316) 681-0295 OPERATORS LICENSE NO. 3710

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? yes If not, is well log attached? w/CP1

Producing formation Aunt Depth to top 3189 bottom 3191 T.D. 3191

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Aunt</u>				<u>4 1/2</u>	<u>3189</u>	<u>2025</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dropped rock to 50' above open hole topped w/4 sacks of cement.
Top Plug- Had pump truck pump 110 sacks of cement to 50' below surface. Came back next day cement fill filled rest of way w/ Ready Mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jonathan Oil Co. License No. 4231
Address 804 N. Haverhill Ct Dorado Ks, 67042.

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KS COUNTY OF BUTLER, ss. 9-16-88

R L KROHBIEL (employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R L Krohbiel

(Address) Wichita

SUBSCRIBED AND SWORN TO before me this 14th day of Sept, 1988

Marietta Brown
Notary Public

MARIETTA BROWN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 9/19/90

My Commission expires: 9/19/90

STATE CORPORATION COMMISSION

FEB 29 1988

CONSERVATION DIVISION
Wichita, Kansas

2

WALNUT VALLEY OIL INC
150 S ROCK RD

WICHITA, KS 67207

#1 ERDWIEN

11-26-2E
35' N. SE SW SW

CONTR ASPEN OIL INC

CTY SEDGWICK

GEOL BOB BRADEN

FIELD GREENWICH

E 1374 KB CM 8/20/80

CARD ISSUED 10/9/80

P 18 BOPD, TR WTR
HUNT OH 3189-91

+	+	+
+	+	+
+	+	+

API 15-173-20,260

SMP	TOPS	DEPTH	DATUM
KC LM		2406	-1032
B KC		2562	-1188
MISS CHT		2878	-1504
KIND SH		3132	-1758
HUNT LM		3189	-1815
RTD		3191	-1817
NO LOG			

8-5/8" 210, 4 1/2" 3189/100SA

OST (1) 3171-3191 (HUNT)/30-30-60-30,
REC 870' CL. O, 210' HOCM, 210'
OCSW, (GR 40), SIP 1189-1190#, FP
112-236/264-483#, HP 1650-1600#
MICT - CO, (HUNT OH), NAT, POP

least lower - check out let
2/26/88 - no lines
87 to 88
(level)

LT ERDWIEN
1032 N. Franklin Ave
Wichita, KS
118

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS