

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County. Sec. 11 Twp. 26S Rge. 2 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW SE SE

Lease Owner Murfin Drilling Company

Lease Name Wisekirch Well No. 3

Office Address 617 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 2-23 19 55

Application for plugging filed 7-19 19 60

Application for plugging approved 7-20 19 60

Plugging commenced 7-25 12:00 Noon 19 60

Plugging completed 7-27 5:30 P. M. 19 60

Reason for abandonment of well or producing formation _____

stopped producing

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Lee N. Guthrie

Producing formation Mississippi Chat Depth to top 2865 Bottom 2871 Total Depth of Well 2871 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	84'	circulated
				5 1/2"	2865'	2437'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 2871 to 2850
Dumped 5 sacks cement
Set 20' rock bridge at 200', dumped 35 sx cement
Mudded hole to 35', set 5' rock bridge
dumped 10 sacks cement.
Welded cap on surface.

RECEIVED
STATE CORPORATION COMMISSION
8-1-60
AUG 1 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kent Well Servicing Company, Inc.
Address Box 667, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Payne

SUBSCRIBED AND SWORN to before me this 29 day of July 19 60

My commission expires June 18, 1963

(Address) Eschelon C. Phillips
Notary Public.



WELL LOG

COMPANY **Murfin Drilling Co.**

FARM **Weiskirch**

NO. **3**

R

SECT. **T-26S R-2E**

LOC. **NW SE SE**

TOTAL DEPTH **2871'**

COMM. **2-14-55**


SHOT OR TREATED

CONTRACTOR **Murfin Drilling Co.**

ISSUED

COMP. **2-23-55**

COUNTY **Sedgwick**
KANSAS



ELEVATION

1354 ~~EF-KB~~

1955 ~~RD 2-4~~

PRODUCTION

25 BOPD

CASING

20	10
15	5/8" w/75 sx at 84'
12	6
13	1/2" w/50 sx at 2865'

FIGURES INDICATE BOTTOM OF FORMATIONS

350	Lime
555	Lime - Shale
1570	Shale - Lime
1700	Lime
1900	Shale
2025	Shale - Lime
2325	Lime - Shale
2580	Lime
2695	Lime - Shale
2855	Shale - Lime
2871	T. D.

TOPS:

Lansing	2195'
Kansas City	2390'
Miss Lime	2837'
Miss Chat	2867'

DRILL STEM TEST #1 - 2864 to 2871. Open 45 min., Strong blow throughout test. Recovered 1700' Gas, 260' Clean Oil, 30' Oil cut mud and 60' Muddy water. BHP 762# in 15 minutes.

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1960
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Sedgwick } SS:

I, W. R. Murfin of the Murfin Drilling Company upon oath state that the above and foregoing is a true and correct copy of the log of the No. 3 Weiskirch well.

Subscribed and sworn to before me this 12th day of April 1955

My Commission Expires: 6-1-55

NOTARY PUBLIC