

15-065-00310-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

9/12/66 SEP 12 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Madden-Davis Well No. A-1

Location SE-SE-SW Sec. 16 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3832'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Barnes & Sons Pipe Pulling,

Address: Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 3:00PM Day 7 Month 9 Year 1966

The Above well was plugged as follows:

185'--8 5/8" Surface pipe, cement circulated.  
3868'--5 1/2" Production casing cemented with 75 Sx. Top perforations  
from 3780' to 3783'. Well plugged back to 3672. Perforated in the  
Cedar Hills formations from 1744' to 1790'.

Pulled 5 1/2" casing and

Squeezed well with 35 sacks gel followed by 75 sacks cement. Pump-in  
pressure 200#. Final shut-in pressure 100#.

(Recovered 1094' 5 1/2" Casing)

(Mudding and cementing operations performed by Globe Oil Well Cementing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. D. Nichols  
Well Plugging Supervisor

DATE 9-12-66

INV. NO. 3904-W