

15-065-02781-02-08

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 142-21

LOCATION NE NE NE

SEC. 16 TWP. 8 RGE. 25 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Paxton Paxson

Operator Champlin Oil & Refg Co Address 306 Koch Bldg Wichita,

Field \_\_\_\_\_ County Graham

Total Depth 3965 Feet.

Plugging Contractor Miller Casing Pulling

Plugging Contractor's License No. 12

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 213' circulated with cement - 5 1/2" at 3961' with 150 sax  
cement behind. P.B. to ~~3921~~' 3920', perforated 3868'.

Filled with chat to 3850', set 4 sax cement with dump bailer,  
pulled 1200' 5 1/2" - pumped hole full commercial mud (40 sax Gel),  
pumped cementing plug to 250', followed by 80 sax cement - cement  
250' to 0'.

Mudding and cementing by Sun Cementing Co, (250# pump pressure )

*Edward Leedy*  
District Conservation Agent

Date 2-17-57

**PLUGGING**  
FILE SEC 16 T 8 R 25 W  
BOOK PAGE 142 LINE 21

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 25 1957  
2/25/57  
CONSERVATION DIVISION  
Wichita, Kansas