

15-065-02784-00-00

Form CP-3
Rev. 6-26-62

KANSAS

AP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Madden-Davis Well No. A-7

Location CN/2-NW-SW Sec. 16 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3807

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Company,

Address: Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 12:30 PM Day 1 Month 8 Year 1968

The Above well was plugged as follows:

200'--8 5/8" Surface pipe, cement circulated.
3797'--5 1/2" Production casing cemented with 100 Sx.

Sanded well back to 3775' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well with initially 11 sacks gel plus 5 sacks hulls and followed with 100
Sx. cement from 1180' to 860' then 16 sacks of gel from 860' to 220' and followed with
20 Sx. cement from 220' to 160' then 3 sacks of gel from 160' to 40' and finally 10 Sx.
cement from 40' to bottom of cellar. Maximum pump-in pressure--350#. Final shut-in
pressure--100#. (Cementing and mudding operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1968
CONSERVATION DIVISION
Wichita, Kansas

Signed: *M. L. Piche*
Well Plugging Supervisor

INVOICED

DATE 8/12/68

INV. NO. 8257-W

8/12/68