

KS-065-02254-00-20
DISTRICT CONSERVATION AGENT'S REPORT

BR

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION NE NE NE
SEC. 17 TWP. 8 RGE. 25

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. A-4 Lease Madden - Davis

Operator Texas Co Address Wichita, Kans

Field _____ County Graham

Total Depth 3935 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____
(Describe briefly the manner in which the well was plugged)

10 3/4" at 514' circulated with cement - 7" at 3934' with
100 sax cement behind - Lane Wells plugs to 3735' - perforated at
3710'.

Filled with sand to 3690', set 5 sax cement with dump bailer,
pulled 1190' 7" - mud to 250' - rock bridge and 20 sax cement
mud to 30' - rock bridge and 10 sax cement to bottom collar.

Edna Kelly
District Conservation Agent

Date 1-4-55

STATE CORPORATION COMMISSION

JAN 10 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 17 8 R 25W
BOOK PAGE 88 LINE 37

1/10/55