

15-065-02785-00-00

R

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1966

CONSERVATION DIVISION
Wichita, Kansas

9/12/66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Madden-Davis Well No. B-3

Location SE-SE-SE Sec. 17 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3815

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons Pipe, Pulling,

Address: Box #313, Great Bend, Kansas. License No. 9

Operation Completed: Hour 1:00PM Day 7 Month 9 Year 1966

The Above well was plugged as follows:

163'--8 5/8" Surface pipe, cement circulated.

3803'--5 1/2" Production casing cemented with 75 sacks cement. Open hole completion.

Sanded well back to 3790' and set 5 sacks cement with dump bailer.

Pulled 5 1/2" casing and squeezed well with 35 sacks gel followed with 75

sacks cement. Pump-in pressure 300#. Final shut-in pressure 200#.

(Recovered 1082' 5 1/2" casing)

(Mudding and cementing operations performed by Globe Oil Well Cementing)

I hereby certify that the above well was plugged as herein stated.

Signed: A. D. Nichols
Well Plugging Supervisor

INVOICED

DATE 9-12-66

INV. NO. 3906-W