

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

2/10/66

FEB 10 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drilling Company,
Complete Address: 650 4th National Bank Building, Wichita, Kansas.
Lease Name Madden--Davis Well No. B-4
Location NE-SE-SE Sec. 17 Twp. 8 Rge. (E) (W) 25
County Graham Total Depth 3808
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Barnes & Sons Casing Pulling Company,
Address: 1216 North Lincoln, Russell, Kansas. License No. 9
Operation Completed: Hour 6:00PM Day 5 Month 2 Year 1966

The Above well was plugged as follows:

171'--8 5/8" Surface pipe, cement circulated with 110 Sx.
3798'--5 1/2" Production casing cemented with 75 Sx. Top perforations @
3670'.
Sanded well back to 3650' and set 5 Sx. cement with dump bailer.
Squeezed well with 25 Sx. gel followed with 100 Sx. cement. Pump-in
pressure 250#. FSIP 100#. It was agreed with Mr. White that a measuring
line would be run on the well after cement set and well would be filled
to bottom of cellar with cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 2/10/66
INV. NO. 2709-U