

15-065-0027-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas

5/24/71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #352, Russell, Kansas.

Lease Name Walts <sup>KCC</sup> Waltz <sup>ZAP</sup> Well No. A-1

Location SW-NW-NE Sec. 25 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3900'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Ralph Comstock Casing Pulling, Incorporated,

Address 320 South Park, Stafford, Kansas. License No. 490

Operation Completed: Hour 4:00 PM Day 20 Month 5 Year 1971

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated with 130 Sx.  
3899'--5 1/2" Production casing cemented on bottom with 125 Sx. 5 1/2" has been squeezed  
@ 2062' with 425 Sx. cement. Well plugged back to 3875'. Top perforations @ 3831'.

Pushed plug to 3800', sanded back to 3775' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 4 sacks hulls and 13 sacks gel  
and followed with 115 Sx. cement from 1175' to 800' then 14 sacks gel from 800' to  
240' and followed with 1 sacks hulls from 240' to 200' then 25 Sx. cement from 200'  
to 125' then 3 sacks gel from 125' to 25' and finally 10 Sx. cement from 25' to 0'.

Maximum pump-in pressure-300#. Final shut-in pressure-200#. (Mudding and cementing  
operations by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 5-24-71

INV. NO. 3735-W