

15-065-01351-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John O. Farmer, Incorporated,  
Complete Address Box #352, Russell, Kansas.  
Lease Name ~~Watts~~ <sup>KCC</sup> ~~Watts~~ <sup>KCC</sup> ~~Watts~~ <sup>ZAP</sup> Watts Well No. B-1  
Location NE-SW-NE Sec. 25 Twp. 8 Rge. (E) (W) 25  
County Graham Total Depth 3950'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Ralph Comstock Casing Pulling, Incorporated,  
Address 320 South Park, Stafford, Kansas. License No. 490  
Operation Completed: Hour 2:45 PM Day 20 Month 5 Year 1971

The above well was plugged as follows:

161'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3949'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug back indicated.  
Top perforations @ 3883'.

Pushed plug to 3800', sanded back to 3775' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 4 sacks hulls and 13 sacks gel and  
followed with 115 Sx. cement from 1175' to 800' then 14 sacks gel from 800' to 240'  
and followed with 1 sack hulls from 240' to 200' then 25 Sx. cement from 200' to 125'  
followed with 3 sacks gel from 125' to 25' and finally 10 Sx. cement from 25' to 0'.

Maximum pump-in pressure-200#. FSIP-100#. (Mudding and cement by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 5-24-71

INV. NO. 3734-U