

15-065-02249-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 40-11
LOCATION NE SW SE
SEC. 25 TWP. 8 RGE. 25

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date-completed supervision of plugging of: _____

Well No. 1 Lease Schamberger "B"
Operator I. W. Siegel et al Address Sterling Drg Co Sterling, Kans
Field _____ County Graham

Total Depth 3900 Feet.

Plugging Contractor R & D Casing Pulling & Sun Cementing Co

Plugging Contractor's License No. 236

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" 253' circulated with cement - 5 1/2" at 3895' with 75 sax
cement behind.

Sand back to 3880', set 4 sax cement with dump bailer, pulled 1390'

5 1/2" to 1100', circulated hole with 40 sax commercial mud (gel) -

Set cementing plug at 650', displaced 25 sax cement through 5 1/2" at

650', - heavy mud to 240', displaced 20 sax cement through 5 1/2" at

240', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Eldon Peely
District Conservation Agent

Date 9-28-57

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 - 1957

CONSERVATION DIVISION
Wichita, Kansas

10/1/57

PLUGGING
FILE SEC. 25 T. 8 R. 25N
BOOK PAGE 40 LINE 11