

15-065-02793-00-01

Form CP-3  
Rev. 6-4-68

KANSAS

*Y*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

4/14/72 APR 14 1972

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,

Complete Address Box #922, Great Bend, Kansas.

Lease Name Schamberger Well No. C-1 Tract #1, Well #1

Location SE-SE-SE Sec. 25 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3970'

Abandoned Oil Well      Gas Well      Input Well X SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:30 AM Day 8 Month 4 Year 1972.

The above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated with 175 Sx.

3964'--5 1/2" casing cemented on bottom with 75 Sx. Top of perforations @ 3950'.

Sanded well back to 3925' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing

(1215') and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed

with 110 Cu. Ft. cement from 1225' to 900' then 16 sacks gel from 900' to 260' and

followed with 30 Cu. Ft. cement from 260' to 185' then 4 sacks gel from 185' to 25'

and finally 10 Cu. Ft. cement from 25' to bottom of cellar. (Maximum pump-in press-

ure--300#. Final shut-in pressure--150#. Mudding and cementing operations by Hallibur-

ton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 4/17/72

INV. NO. 5362-U