

15-065-20375-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1970
CONSERVATION DIVISION
Wichita, Kansas

10/7/70

Operator's Full Name John O. Farmer, Incorporated.
Complete Address 370 West Wichita Avenue, Russell, Kansas.
Lease Name Walts Well No. 3
Location SE-NE-NE Sec. 25 Twp. 8 Rge. (E) (W) 25
County Graham Total Depth 3970'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 2:45 AM Day 5 Month 10 Year 1970

The above well was plugged as follows:

205'--8 5/8" Surface casing, cement circulated with 135 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru
DP from 1225' to 900'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 10/7/70

INV. NO. 2043-W