

15-065-20628-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
8/28/73 AUG 28 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Levitt, et al,

Complete Address Century Plaza, Wichita, Kansas.

Lease Name L & R Schamberger Well No. 2

Location CNE-SW Sec. 25 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3955'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address 905 Century Plaza, Wichita, Kans. License No.

Operation Completed: Hour 11:00 AM Day 24 Month 8 Year 1973

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 110 Cu. Ft. cement
thru DP from 1150' to 825'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru DP
from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/30/73

INV. NO. 7844-A

Signed: A. L. Nichols
Well Plugging Supervisor