

15-065-00007-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1962

CONSERVATION DIVISION
Wichita, Kansas
1/17/62

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: SW SE SE Sec. 26 Twp. 8 Rge. _____ (E) _____ (W) 25

Name of Field: _____ Total Depth: 4022

I have this date completed supervision of plugging of:

Lease Name: Minium Well No. 1

Operator's Full Name: Empire Drg Co

Complete Address: 407 Brown Bldg Wichita, Kansas

Plugging Contractor Barnes & Sons

Address: Russell, Kansas License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 13 Month 1 Year 62

The above well was plugged as follows:

8 5/8" 143' circulated with cement - 5 1/2" 4018' with 75 sax cement.

Sand to 3950' - set 4 sax cement with dump bailer - pulled 2000' 5 1/2"

to 500' circulated hole with heavy mud through 5 1/2" (35 sax Gel),

displaced 20 sax cement through 5 1/2" at 500', heavy mud to 180',

displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set

bridge and filled to bottom cellar with cement.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 2/2/62
INV. NO. 4440-W