

15-065-20148-0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 17 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
6/17/68

Operator's Full Name Chief Drilling Company Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Minium Well No. 2

Location 150' N of CSE-SE Sec. 26 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 4060'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 5:00PM Day 9 Month 6 Year 1968

The Above well was plugged as follows:

227'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Squeezed well with 130 Sx. cement from 1300' to 980' then 18 sacks gel from 980' to

240' and followed with 20 Sx. cement from 240' to 180' then 3 sacks gel from 180' to

40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure

350#. Final shut-in pressure--200#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. S. Nichols  
Well Plugging Supervisor

DATE 6/17/68  
INV. NO. 7951-W