

DISTRICT CONSERVATION AGENT'S REPORT
15-065-00948-00-00

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 41-13
LOCATION SW SW NE
SEC. 28 TWP. 8 RGE. 25

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease ^{KCC 2147} J. Searl

Operator Continental Oil Co Address Box 98 Plainville, Kans

Field _____ County Graham

Total Depth 4050 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 240' circulated with cement - 5 1/2" 4049' with 100 sax
cement behind - P.B. to 3940', perforated 3866' and 3806'.

Filled with sand to 3790', set 4 sax cement with dump bailer, pulled
3400' 5 1/2" to 680', circulated hole with heavy commercial mud at 680',
displaced 35 sax cement through 5 1/2" at 600', heavy mud to 35', set
rock bridge and filled with cement to 0'.

Mudding and Cementing by Halliburton Cementing Co.

E. J. Searl
District Conservation Agent

9-6-57
Date _____

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1957
CONSERVATION DIVISION
Kansas

9-9-57

PLUGGING
FILE SEC 28 T 8 R 25 W
BOOK PAGE 41 LINE 13