

KANSAS

20
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20149-0000

6-16-68
RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bankoff & Leben,

Complete Address: Drawer # 2479, Tulsa, Oklahoma.

Lease Name Culley Well No. 1

Location NW-SE-NW Sec. 28 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3885

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box # 486, Great Bend, Kansas. License No.

Operation Completed: Hour 3:00PM Day 6 Month 6 Year 1968

The Above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota Section @ 1010'.

Circulated hole with heavy mud. Pulled DP to 1235' and displaced 100 Sx. cement thru
DP from 1235' to 910'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from 210'
to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Deibel*
Well Plugging Supervisor

DATE 6/10/68
INV. NO. 7923-W