

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20335-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 7 1972 9-7-72  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bankoff Oil Company,

Complete Address 1119 Sherman, Great Bend, Kansas.

Lease Name Culley Well No. 1

Location NW-NW-SE Sec. 28 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 4042'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:00 M Day 5 Month 9 Year 1972

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated.

4038'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4010'. Top of perforations @ 3872'.

Sanded well back to 3850' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (2830') and squeezed well initially with 5 sacks hulls and 13 sacks gel and followed with 110 Cu. Ft. cement from 1300' to 975' then 19 sacks gel from 975' to 225' and followed with 30 Cu. Ft. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure --500#. Final shut-in pressure--200#. (Mudding and cementing operations by Globe).

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 9/7/72  
INV. NO. 6283-W