

KANSAS

14 STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1973

CONSERVATION DIVISION
Wichita, Kansas

7-9-73

13-065-20613-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Woodman & Iannitti Drilling Company.

Complete Address 1008 Union National Building, Wichita, Kansas.

Lease Name Culley Well No. 1

Location SE-NW-SE Sec. 28 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3998

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor John O. Farmer, Incorporated,

Address 370 W. Wichita, Russell, Kansas. License No. _____

Operation Completed: Hour 5:00 PM Day 5 Month 7 Year 1973

The above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with 130 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 7/10/73
INV. NO. 7608-U