

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-065-21, 674-00-00 ^P

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Helberg Oil Co. Lic. # 5669

Complete Address Box 32, Morland, Ks. 67650

Lease Name Helberg Well No. 1

Location SE NW SE Sec. 31 Twp. 8 Rge. 25 (East) (West) (West)

County Graham Total Depth 2508'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Helberg Oil Co.

Address Box 32, Morland, Ks. 67650 License No. 268

Operation Completed: Hour: 3:00 PM Day: 14 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: ~~All~~ Part _____ None

The above well was plugged as follows:

8 5/8" 208' SP. case w/135 sacks cement - 2% Incl. - 3% cal. cl.

Ordered 160 sacks 50% permix - 4% Incl. - 3% cal. cl. + 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug C 1350' w/100 sacks.

2nd plug C 250' w/40 sacks.

3rd plug - solid bridge of hulls + plug C 40' w/10 sacks.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 208' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

~~_____~~
~~_____~~
~~_____~~

INVOICED
DATE 11-15-82
INV. NO. 1578-W

Signed: _____
Conservation Division Agent

STATE CORPORATION COMMISSION
RECEIVED
SEP 27 1982
CONSERVATION DIVISION
Wichita, Kansas
9-27-82

[Handwritten mark]