

KANSAS

*2*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 5 1973  
3-5-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,  
Complete Address R. R. #2, Victoria, Kansas.  
Lease Name Ziegler Well No. 2  
Location NW-SE Sec. 30 Twp. 8 Rge. (E) (W) 26  
County Sheridan Total Depth 3980'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Russ Casing Pulling, Incorporated,  
Address Box #1082, Great Bend, Kansas. License No. 623  
Operation Completed: Hour 3:00 PM Day 28 Month 2 Year 1973

The above well was plugged as follows:

176'--8 5/8" Surface casing, cement circulated.  
3981'--4 1/2" Production casing cemented on bottom with top of cement @ 3150'. Top of perforations @ 3717'.

Pushed plug to 3700' and sanded back from 3700' to 3650'. Set 4 Sx. cement on top of plug with dump bailer. Pulled 4 1/2" casing (1500') and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed with 110 Cu. Ft. cement from 1250' to 925' then 17 sacks gel from 925' to 225' and followed with 30 Cu. Ft. cement from 225' to 150'. Then 3 sacks gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar. (Mudding and cementing operations by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Jickel*  
Well Plugging Supervisor

INVOICED

DATE 3/5/73  
INV. NO. 7098-u