

KANSAS

*Handwritten initials*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 7 1972  
CONSERVATION DIVISION  
Wichita, Kansas

*Handwritten: 50 0000 2-7-1972*

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Dreiling Oil, Incorporated,  
 Complete Address R. R. #2, Victoria, Kansas.  
 Lease Name Sutor Well No. 4  
 Location NW-NW Sec. 30 Twp. 8 Rge. (E) (W) 26  
 County Sheridan Total Depth 3930'  
 Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
 Other well as hereafter indicated \_\_\_\_\_  
 Plugging Contractor Above  
 Address \_\_\_\_\_ License No. \_\_\_\_\_  
 Operation Completed: Hour 7:00 PM Day 1 Month 2 Year 1972

The above well was plugged as follows:

163'--8 5/8" Surface casing, cement circulated with 125 Sx.  
3922'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3862'.  
Top of perforations @ 3804'.  
Sanded well back to 3775' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and  
squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with 110 Cu.  
Ft. cement from 1200' to 875' then 17 sacks gel from 875' to 200' and followed with 30  
Cu. Ft. cement from 200' to 125' then 2 sacks gel from 125' to 40' and finally 10 Cu. Ft.  
cement from 40' to bottom of cellar. Maximum pump-in pressure-400#. Final shut-in press-  
ure-200#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. B. Deibel*  
Well Plugging Supervisor

DATE 2/11/72  
INV. NO. 5148-W