

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1968
CONSERVATION DIVISION
Wichita, Kansas
9-18-1968

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name Sutor Well No. 5

Location NE-SE Sec. 30 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 3973

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leo J Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.

Operation Completed: Hour 4:00AM Day 16ⁿ Month 9 Year 1968

The Above well was plugged as follows:

185'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1055'.

Circulated hole with heavy mud. Pulled DP to 1285' and displaced 100 Sx. cement thru
DP from 1285' to 960'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. S. Nichols
Well Plugging Supervisor

INVOICED
DATE 9/18/68
INV. NO. 8478-W