

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1967
7-3-1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name Pratt Well No. 1

Location Appr. CNW-SE Sec. 32 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 2237

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company,

Address: Rte. #2, Great Bend, Kansas. License No. _____

Operation Completed: Hour 5:30PM Day 28 Month 6 Year 1967

The Above well was plugged as follows:

This well drilled to Anhydrite and abandoned. No surface pipe, 7 7/8" hole. Circulated hole with heavy mud, set plug @ 1300' and displaced 135 Sx. cement thru DP leaving top of cement plug @ appr. 500'. Pulled DP. to 210' and circulated cement to bottom of cellar with 65 Sx. Used 4% gel in all cement for weight and volume control.

(Cementing operations performed by Globe Oil Well Cementing Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols

Well Plugging Supervisor

DATE 8/3/67

INV. NO. 5505-W