

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1975  
11-3-1975  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil Inc.  
Complete Address RT. 1 Box 28 Victoria Ks.  
Lease Name Hoxie State Bank Well No. #1  
Location SE-SE-SE Sec. 32 Twp. 8 Rge. 24 (E) (W) X  
County Sheridan Total Depth 3870  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Dreiling Oil Inc.  
Address RT #1 Box 28 Victoria Ks. License No. \_\_\_\_\_  
Operation Completed: Hour 2:00 PM Day 31 Month Oct. Year 1975

The above well was plugged as follows:

KB. 2517' D&K Top. 1550', S.P. 175' of 8 5/8" cwc 175 x  
4 1/2" casing set @ 3863' w/125 sx cem.  
Top of Cem. 3150', Top Pers. 3868' Bottom Plug  
set @ 3600' w/50' of sand & 4 sx cem.  
Recovered 1706' of 4 1/2" casing. Pumped down 8 5/8"  
casing. 3 sx. Halls. 80. sx cem. 50/50 Pozmix 4% Gel.  
13 sx Gel. Release Plug & 50 sx cem. 50/50 Poz. 6% Gel.  
Max Pres. 500 Lbs. Closing Pres. 500 Lbs. Sun. Cementing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. L. Balthazar  
Well Plugging Supervisor

DATE 11/3/75  
INV. NO. 2175-W