

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 22 1973  
8-22-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Hinkle Oil Company,

Complete Address 1016 Union Center, Wichita, Kansas.

Lease Name Senger Well No. 1

Location NE-NE-NW Sec. 34 Twp. 8 Rge. (E) (W) 26

County Sheridan Total Depth 4440'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling,

Address P. O. Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 12:30 PM Day 18 Month 8 Year 1973

The above well was plugged as follows:

172'--8 5/8" Surface casing, cement circulated.

3965'--5 1/2" Production casing cemented on bottom with 170 Sx. Well plugged back to 3768'. Top perforations from 3661' to 3658.

Pushed plug to 3650', sanded from 3650' to 3625' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing (2518') and attempted to squeeze well. Pumped in 5 sacks hulls and 9 sacks gel and gained circulation around surface casing. Called Service Rig and ran 2 1/2" tubing to 250', hit bridge. Called pump truck and washed tubing to 1000' and there circulated gel. Pulled tubing to 975' and displaced 110 Cu. Ft. cement thru tubing. Pulled tubing to 185' and displaced 30 Cu. Ft. cement thru Tubing. Pulled tubing and filled hole from 25' to bottom of cellar with cement. (Mudding and cementing operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/24/73

INV. NO. 7812-W

Signed: A. L. Dickels  
Well Plugging Supervisor