

15-179-20232-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1969
CONSERVATION DIVISION
Wichita, Kansas
10/1/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Jerome Well No. A-1

Location NE-NE-SW Sec. 35 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 3955'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 5:30 AM Day 29 Month 9 Year 1969

The above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru
DP from 1300' to 975'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/1/69

INV. NO. 572-W

Signed: M. L. Dickel
Well Plugging Supervisor