

6 031140

7-25

353

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,462-00-00P

SE SE SW, SEC. 23, T 8 S, R 24 W/Ex

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Gates Well # 1

Operator: Viking Resources

County Graham 126.75

Name & Address 120 S. Market Suite 518

Well Total Depth 3900 feet

Wichita, Kansas 67202-3818

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mallard JV Inc. License Number 4958

Address McPherson, Ks.

Company to plug at: Hour: AM Day: 25 Month: July Year: 19 88

Plugging proposal received from Jamie Hess

(company name) Mallard (phone)

were: 8 5/8" set at 227' w/160 sks cwc. Circ. hole from bottom. Spot cement

plugs w/drill pipe and ballance plugs w/mud of no less than 36 vis. w/no loss or gain of fluids.

Order 200 sks 60/40 Poz 6% Gel 3% C C 8 5/8" wiper plug. Allied Cement. Keller Water

Truck from Irrigation.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 6:45AM Day: 25 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2025' w/25 sks

1000' w/100 sks and 1 sk Hulls

280' w/40 sks

40 sks w/10 sks wiper plug

15 sks in rathole

10 sks in mouse hole

RECEIVED STATE CORPORATION COMMISSION SEP - 6 1988 CONSERVATION DIVISION Wichita, Kansas

9-6-88

Remarks: Elevation 2303' KB Anhy 2020' -51' (if additional description is necessary, use BACK of this form.)

INVOICED (if applicable) observe this plugging.

DATE 9-8-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 22173