

4-031872

10-27 15-065-02722-0001

E-09,577

API number: 15- - 1956

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE SE /4 SEC. 31, 08 S, 24 W
330 feet from S section line
990 feet from E section line

Operator license# 30420

Lease Holley well # 8-5

Operator: V.J.I. Resources

County Graham

Address: 1503 Vine Street
Hays, Kansas 67601

Well total depth 3936 feet 127.92
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well ____, Gas well ____, Input well X, SWD ____, D & A ____

Plugging contractor: Allied Cement Company

License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 27 Month: October Year: 93

Plugging proposal received from: Jason Dinges

Company: V.J.I. Resources

Phone: _____

Were: Order 350 sxs. 65/35 pozmix - 10% gel - 500# hulls.
Fluid level low hole open to perms.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 4:00P.M., Day: 27, Month: October, Year: 93

Actual plugging report: 8 5/8" set @ 250' w/175 sxs. cwc. 5 1/2" set @
3936' w/250 sxs. D.V. set @ 2158' w/275 sxs. cwc. Prod. Perfs. 3922'-3945'.
Squeezed 8 5/8" w/50 sxs. to Max. P.S.I. 200#. Close in P.S.I. 200#.
Squeezed 5 1/2" w/300 sxs. cement blend w/450# hulls mixed in to Max.
P.S.I. 1000#. Close in P.S.I. 400#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD ____, BAD ____, Anhy. plug: YES X NO

Bottom plug(in place): YES ____, CALC X, NO ____, Dakota plug: YES X, NO

Plugged through TUBING ____, CASING X. Elevation: _____

I did [X] / did not [] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED
NOV 05 1993
11-5-1993
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 11-8-93
INV. NO. 39170

DEC 30 1993