

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00438-00-00  
Spot: CSWSWSW Sec/Twnshp/Rge: 10-8S-25W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: WALTS Well Number: 1  
County: GRAHAM Total Vertical Depth: 3965 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

Conductor Pipe: Size feet: \$128.86  
Surface Casing: Size 8.625 feet: 150  
Production: Size 5.5 feet: 3944  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/21/2001 11:00 AM  
Plug Co. License No.: 8914 Plug Co. Name: H & C OIL OPERATING INC.  
Proposal Rcvd. from: CHARLES RAMSAY Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered out 345 sxs 60/40 pozmix - 10% gel with 500# hulls.  
5 1/2" set at 3944'. PBTD 3880'.  
No squeeze records.  
Casing leak Dakota 1000' - 1100'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/21/2001 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated anhydrite at 2130' - 2 shots.  
Ran tubing to 2140'.  
Allied pumped 170 sxs 60/40 pozmix - 10% gel with 300# hulls - lost circulation.  
Pulled tubing to 1400'.  
Allied pumped 115 sxs with 200# hulls - cement circulated.  
PTOH. Allied squeezed with 15 sxs.  
Max. P.S.I. 500#. S.I.P. 500#.  
Hooked up to backside. Allied pumped 50 sxs.  
Max. P.S.I. 100#. S.I.P. 100#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

RECEIVED

NOV 28 2001 11/28/01

KCC WICHITA

INVOICED

DATE 11-29-01

INV. NO. 2002060996

Form CP-2/3

NOV 26 2001

WENTWORTH DRILLING

#1 WALTERS

10-8-25W  
SW SW SW

Contr. WENTWORTH DRLG

GRAHAM County

E 2403 REComm.

Comp. 10-8-54

IP 175 BOPD

PERM PMP

| Tops | Depth | Datum |
|------|-------|-------|
|      |       |       |
| TOP  | 3470  | -1067 |
| HEEB | 3680  | -1277 |
| TOR  | 3702  | -1299 |
| LANS | 3720  | -1317 |
| B/KC | 3930  | -1527 |
|      |       |       |
|      |       |       |
|      |       |       |
| TD   | 3965  | -1562 |

Casing

8" 150

5" 3944

1/2 BOPH & WTR: PB 3880:  
PERF 24/3867-92: 125 B0  
24 HRS: FLO 14 BOPH

SCHMIED NE POOL

|  |  |  |
|--|--|--|
|  |  |  |
|  |  |  |
|  |  |  |
|  |  |  |

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

10/25/94  
MAOICEP