

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01942-00-01
Spot: CNESWSW Sec/Twnshp/Rge: 10-8S-25W
990 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: WALTS Well Number: 3
County: GRAHAM Total Vertical Depth: 3855 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

Conductor Pipe: Size feet: 3125.29
Surface Casing: Size 8.625 feet: 117 150 sx cmt
Production: Size 5.5 feet: 3820 200 sx cmt
Liner: Size feet:

Well Type: WSW UIC Docket No: E20461.1 Date/Time to Plug: 11/21/2001 3:00 PM

Plug Co. License No.: 8914 Plug Co. Name: H & C OIL OPERATING INC.

Proposal Rcvd. from: CHARLES RAMSAY Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered out 180 sxs 60/40 pozmix - 10% gel with 300# hulls.
PBTD 1890'.
Converted to WSW Cedar Hills.
Perfs 1650' - 1820'. Fluid Level 375'.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/21/2001 4:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1600'.
Allied pumped 110 sxs 60/40 pozmix - 10% gel with 500# hulls - cement circulated.
PTOH. Allied squeezed with 45 sxs.
Max. P.S.I. 1000#. S.I.P. 1000#.
Released pressure.
Hooked up to backside. Instant pressure 500#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

RECEIVED

NOV 28 2001

KCC WICHITA

INVOICED

DATE 11-29-01

INV. NO. 2002060996

NOV 26 2001

LEO WENTWORTH

#3 WALTERS

10-8-25W
NE SW SW

Contr. LEO WENTWORTH GRAHAM County


E 2338RB Comm. Comp. 11-18-55 IP 125 BOPD
PERM PMPG

Tops	Depth	Datum
HEEB	3620	-1282
LANS	3658	-1320
TD	3855	-1517

Casing
8" 117 w/150 SX
5" 3820 w/200 SX

PERF 3801-08: ACID 1500
SWB 18 BOPH/5 HR

SCHMIED NE POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

10/20/11