

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20769-00-00  
Spot: CSWSESW Sec/Twnshp/Rge: 10-8S-25W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: WALTS Well Number: 4  
County: GRAHAM Total Vertical Depth: 3880 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

Conductor Pipe: Size feet: \$126.10  
Surface Casing: Size 8.625 feet: 209 150 SX CMT  
Production: Size 4.5 feet: 3885 150 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/21/2001 8:30 AM  
Plug Co. License No.: 8914 Plug Co. Name: H & C OIL OPERATING INC.  
Proposal Rcvd. from: CHARLES RAMSAY Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
4 1/2" set at 3885' w/150 sxs.  
No squeeze records.  
PBTD 3858'. Fluid Level 1100'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/21/2001 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated anhydrite 2100'. Casing leak at 1200' Dakota.  
Ran tubing to 2200'.  
Allied pumped 110 sxs 60/40 pozmix - 10% gel with 300# hulls - cement circulated.  
PTOH. Allied squeezed with 60 sxs cement and 200# hulls.  
Max. P.S.I. 800#.  
Hooked up to backside. Allied pumped 50 sxs cement.  
Max. P.S.I. 200#. S.I.P. 100#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

110  
RECEIVED

NOV 28 2001

KCC WICHITA

11/28/01  
INVOICED

DATE 11-29-01

INV. NO. 2002060996

Form CP-2/3

NOV 26 2001

