

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21527-00-00
Spot: CNENESW Sec/Twnshp/Rge: 10-8S-25W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: WALTS Well Number: 5
County: GRAHAM Total Vertical Depth: 3970 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

Conductor Pipe: Size feet: 8129.03
Surface Casing: Size 8.625 feet: 238 150 SX CMT
Production: Size 4.5 feet: 3943 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/20/2001 12:30 PM

Plug Co. License No.: 8914 Plug Co. Name: H & C OIL OPERATING INC.

Proposal Rcvd. from: CHARLES RAMSAY Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
4 1/2" set at 3943' w/150 sxs.
No squeeze records.
Perforated anhydrite at 2110'. Dakota casing leak.
Fluid Level 750'. PBTD 2800'. Solid.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 11/20/2001 3:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2200'.
Allied pumped 135 sxs 60/40 pozmix - 10% gel with 300# hulls - cement circulated.
PTOH. Allied squeezed with 75 sxs cement and 200# hulls.
Max. P.S.I. 1000#. S.I.P. 600#.
Hooked up to backside.
Allied pumped 50 sxs. Max. P.S.I. 0#, followed with 50 sxs cement and 200# hulls.
Max. P.S.I. 0#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

11/28/01 NOV 28 2001

KCC WICHITA

INVOICED

DATE 11-29-01

INV. NO. 2002060996

NOV 26 2001

