

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22091-00-01
Spot: SESESW Sec/Twnshp/Rge: 10-8S-25W
390 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: WALTS Well Number: 6
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

Conductor Pipe: Size feet: 8/26.75
Surface Casing: Size 8.625 feet: 254 200 SX CMT
Production: Size 4.5 feet: 3899 150 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E20461.2 Date/Time to Plug: 11/20/2001 9:00 AM
Plug Co. License No.: 8914 Plug Co. Name: H & C OIL OPERATING INC.
Proposal Rcvd. from: CHARLES RAMSAY Company: H & C OIL OPERATING INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered out 230 sxs 60/40 pozmix - 10% gel - 500# hulls.
4 1/2" set at 3899' w/150 sxs.
D.V. Tool at 2043' w/325 sxs.
W.L.M. PBTB 3735'. Fluid Level 725'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/20/2001 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2200'.
Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls - cement circulated.
PTOH. Allied squeezed 15 xs.
Max. P.S.I. 1000#. S.I.P. 1000#.
Hooked up to backside - instant pressure 500#.

Remarks: LEASE READS AS FOLLOWS: 60°N.CSESESW 10-08-25W. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

RECEIVED

NOV 28 2001

KCC WICHITA

INVOICED

DATE 11-29-01

INVOICE NO. 2002060996

Form CP-2/3

NOV 26 2001

11/58/85

HELMERICH & PAYNE, INC

P.O. Box 238

#6 WALT

10-8-25W

GARDEN CITY, KS 67846

60' N.


C SE SE SW

CONTR PIONEER DRILLING

CTY GRAHAM

GEOL ALAN DOWNING

FIELD SCHMIED NE



ELV 2332 KB SPD 11/14/84

CARD ISSUED 3/21/85

IP P 10 B0 & 41.5 BWPD

2327 GL

DRLG COMP 11/20/84

LKC 3794-3799

LOG	Tops	Depth/Datum
ANH	2046+ 286
TOP	3371-1039
HEEB	3607-1275
TOR	3631-1299
LANS	3647-1315
LKC I	3794-1462
BKC	3859-1527
PBTD	3883-1551
RTD	3900-1568

API 15-065-22,091

8 5/8 " 254 / 200SX, 4 1/2 " 3899 / 150SX, FO TOOL AT 2043 / 325SX

DST (1) 3786-3805 (LKC) / 15-30-30-60, REC 2' CL OIL, 62' OCMW (CHL 1500 PPM), SIP 423-434#, FP 63-63 / 63-63#, HP 1981-2043

MICT - CO, PF (LKC I) 3794-3799, W / 2 SPF, AC 250G (15% MCA), SWB DWN, RE-AC 1000G (60-QUAL DGA 220) & 1000G (40-QUAL DGA 220) SWB DWN, SO, SET 2 3/8 " TBG AT 3849, POP, P 10 B0 & 41.5 BWPD, 1/4/85