

1-6  
4-031888

E-25,136

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-21461-00-01

NW NE NW /4 SEC. 15, 08 S, 25 W  
4950 feet from S section line  
3630 feet from E section line

Operator license# 8914

Lease Ostmeyer well # 1

Operator: H & C Oil Operating, Inc.

County Graham

Address: P.O. Box 86  
Plainville, Kansas 67663

Well total depth 3944 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 204 feet

128.18

Aband. oil well \_\_\_\_, Gas well \_\_\_\_, Input well X, SWD \_\_\_\_, D & A \_\_\_\_

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 6 Month: January Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing Pulling Phone: \_\_\_\_\_

Were: Order 225 sxs. 65/35 pozmix - 10% gel - Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 1:00P.M., Day: 6, Month: January, Year: 94

Actual plugging report: 8 5/8" set @ 204' w/150 sxs. 4 1/2" set @ 3895' w/150 sxs. P.B.T.D. 3883'. Top stage with perf. @ 1875' w/350 sxs - 1730' w/350 sxs.-1410' w/350 sxs.-1200' w/350 sxs.-1090' w/350 sxs. T.O.C. 1055' - Shot @ 2100' anhy. for critical area control. Shot @ 1000' solid. Mix and pump 137 sxs. cement blend displace from 750' to 3826'. Shot at 700' solid. Shot @ 600' solid. Shot @ 500'. Pulled 2 for skid and 2 for rack. Mixed and pumped 175 sxs. to circulate. Pulled 4 1/2" casing. Fill 8 5/8" to cellar. Used total 225 sxs. cement blend.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: 2361 GL

I X did not observe the plugging.

Carl Goodrow  
Wichita, Kansas

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISS

JAN 20 1994

CONSERVATION DIVISION  
Wichita, Kansas

1/20/94

INVOICED

DATE 1-24-94

INV. NO. 39765