

1-5

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-21,871-00-00

NE NE NW /4 SEC. 15, 08 S, 25 W
4950 feet from S section line
2970 feet from E section line

Operator license# 8914 Lease Ostmeyer well # 2

Operator: H & C Oil Operating, Inc. County Graham

Address: P.O. Box 86 Well total depth 3911 feet
Plainville, Kansas 67663 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 276 feet

127.11

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pullers, Inc.g License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 10:00A.M Day: 5 Month: January Year: 94

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 255 sxs. 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1994
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 5, Month: January, Year: 94

Actual plugging report: 8 5/8" to 276'. 4 1/2" to 3872'. Sanded to 3725' and spotted 4 sxs. cement with dump bailer. Shot casing at 2100' and didn't pull free. Mixed and displaced 40 sxs. cement to 1800'. Shot at 1700' and 1250' and didn't pull free. Mixed and pumped 35 sxs. cement w/100# hulls and displaced to 1100'. Shot at 1050' and 850' and didn't pull free. Shot at 613' with free pipe. Pumped 35 sxs. cement with 100# hulls. Pulled casing to 275' and circulated cement to surface with 40 sxs. cement with 100# hulls. Pulled casing and topped with 15 sxs.cmt.

Remarks: Allied Cementing.
Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES X, CALC , NO Dakota plug:YES X, NO
Plugged through TUBING , CASING X. Elevation: 2343 GL

I did [X] / did not [] observe the plugging. [Signature]

INVOICED
DATE 1-24-94
INV. NO. 39766

DA (agent)
Form CP-2/3