

4-071014

10-22

26

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,682-0000

C NE NW /4 SEC. 21, 08 S, 25 W
660 feet from S section line
3300 feet from E section line

Operator license# 5669

Lease Babcock well # 1

Operator: Helberg Oil Company

County Graham

Address: Box 32
Morland, Kansas 67650
Jerry Helberg

Well total depth 3860 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 200 feet

125.45

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Helberg Drilling & B.J. Services License# -

Address: Morland, Kansas 67650 - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 22 Month: October Year: 92

Plugging proposal received from: Jerry Helberg

Company: Helberg Oil Company Phone: 913-627-5665

Were: 8 5/8" - 200' S.P. cwc. w/135 sx. 60/40 pozmix - 6% gel. -
3% c.c. By Allied Cement. K.C. Well - Elv. 2299' - Anhy. 2058'.
Mud condition 37 vis. - 9.2 wt. - 8.8 W.L. No circulation problems.
Proposal 190 sx. 60/40 pozmix - 6% gel. - 1 sx. flocele. Circulate
hole. Spot with drill stem - heavy mud between all plugs.
25 sx. @ 2070' - 100 sx. w/1 sx. F.C. @ 1150' - 40 sx. @ 240' -
10 sx. @ 40' - 15 sx. rathole (cir.) - 10 sx. mousehole (cir.)

Cement by B.J. Services.
Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:00P.M., Day: 22, Month: October, Year: 92

Actual plugging report: Helberg ordered 190 sx. 60/40 pozmix - 6% gel.
1 sx. flocele. Circulated hole, spotted and displaced cement through
drill stem. Heavy mud between all plugs.

1st. plug @ 2070' w/25 sx. cement.
2nd. plug @ 1150' w/100 sx. cement w/1 sx. flocele.
3rd. plug @ 240' w/40 sx. cement.
4th. plug @ 40' w/10 sx. cement.
15 sx. in rathole (cir.) 10 sx. in mousehole (cir.)

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1992
11/19/92
Wichita, Kansas

Remarks: B.J. Services
Condition of casing(in hole):GOOD BAD Anhy.plug:YES NO
Bottom plug(in place):YES , CALC , NO Dakota plug:YES , NO
Plugged through TUBING , CASING . Elevation: 2299 GL

I did[] / did not[] observe the plugging.

Marion J. Schmidt
(agent)

DATE 11-24-92
INV. NO. 36882