

6 070250

API NUMBER 15-065-22, 108-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW-SE-SW, SEC. 27, T. 8 S, R 25 W
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

990 feet from S section line

2630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5342

Lease Name ST. JOHN Well # 1-27

Operator: BENCON EXPLORATION CO.

County GRAHAM 144.92

Name & Address 410 17th ST # 2300

Well Total Depth 4459 feet

DENVER, COLORADO

Conductor Pipe: Size 0 feet

80202

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated TAG # 183

Plugging Contractor FIBERCROMBIE DRUG. INC License Number 5422

Address WICHITA, KANS.

Company to plug at: Hour: 5:00 PM Day: 17th Month: NOV Year: 19 84

Plugging proposal received from WIB. DREILING

(company name) FIBERCROMBIE DRUG. INC (phone) 303-825-1966

were: ORDER 265 5th 5th CLASS "A" - GEL-CH-CL - 1 5th ORLO FLAME AND 8 5/8" PLUG.

SPOT WITH DRILL STEM-TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

CIRCULATION PROBLEMS AT 4360', ARBUCHIE @ 4424' - ELV. 2399 - ANH. 2108'

8 5/8" SP. 218' EUC #1/170 5th CLASS "A" - GEL-CH-CL - 1 5th ORLO FLAME (CEPA BY DOWEX)

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by M. J. Schmidt
BOIC (TECHNICIAN) NOV 26 1984

Plugging Operations attended by Agent?: All X Part None 11-26-84

Operations Completed: Hour: 5:00 PM Day: 17th Month: NOV Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 265 5th CLASS - GEL-CH-CL - 1 5th ORLO FLAME + 8 5/8" PLUG

SPOTTED WITH DRILL STEM-TURNED HOLE OVER; HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 4410 FT #1/30 5th CNT. - 2nd PLUG @ 4290 FT #1/30 5th CNT

3rd PLUG @ 2130 FT #1/30 5th CNT - 4th PLUG @ 1240 FT #1/100 5th CNT #1/54 FLAME

5th PLUG @ 270 FT #1/50 5th CNT, 6th PLUG SOLID BRIDGE MAN'S PLUG @ 40 FT #1/10 5th CNT.

15th IN RAT HOLE CIRCULATE (CEMENTED BY DOWEX CNT)

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 11-28-84 Witnessed By CARL GOODROW

Signed M. J. Schmidt
BOIC (TECHNICIAN) 11-21-84

INV. NO. 4956 11-17-84