

15-179-20004-00-00

R

6030587

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_

SESWNW SEC. 2, T. 8 S, R 26  
2970 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6369

Lease Name NIBLOCK Well # 1

Operator: JOE KATZ OIL ACCOUNT  
Name & Address: 420 S. DIXIE HWY. SE 3B1  
CORAL GABLES, FLORIDA  
33146

County SHERIDAN 126,72  
Well Total Depth 3899 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 207'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HALLIBURTON License Number \_\_\_\_\_

Address OBERLIN, KANSAS

Company to plug at: Hour: PM Day: 22 Month: 10 Year: 19 85

Plugging proposal received from ROGER WELTY

(company name) JOE KATZ (phone) \_\_\_\_\_

were: 8 5/8 SET @ 207' w/155sx. 5 1/2 SET @ 3899 w/125sx. SQUEEZED @ 3037 w/200sx. @ 2476 w/200sx. ORDER 400 SX. 60/40 @ 2 10% GEL. 5 SX. HULLS. HALLIBURTON CEMENT CO. LARUE WATER TRUCK.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:PM Day: 22 Month: 10 Year: 19 85

ACTUAL PLUGGING REPORT PULL RODS & Pump. SCREW ON TO 2 3/8 TUBING MIX. & Pump 100SX. CNT. MIX + 2SX. HULLS LAYDOWN 40 JOINTS OF TUBING SCREW ON TO TUBING MIX. & Pump 100SX. CNT. MIX + 2SX. HULLS. LAYDOWN 40 JOINTS TUBING SCREW ON TO TUBING MIX. & Pump 100SX. CNT. MIX. CEMENT CIRCULATED TO SURFACE LAYDOWN TUBING. 3 1/2 JOINTS FILL 5 1/2 CASING DISPLACEMENT SCREW ON TO BACK SIDE PUMP 1 1/2 SX HULLS + 20SX CNT.

Remarks: MIX. BACKSIDE LOADED AND PRESSURED PLUG. COMPLETE.  
(If additional description is necessary, use BACK of this form.)

12600 PSI @ 5875'

RECEIVED  
STATE CORPORATION COMMISSION  
Signed Carl Goodrow  
(TECHNICIAN)

DATE NOV 12 1985

INV. NO. 10965

NOV 4 1985

CONSERVATION DIVISION