

To: **6 031522**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-29
API NUMBER 15-179-20685-0600

NE SE NE, SEC. 14, T 8 S, R 26 W/Ex
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exp Inc.
Name & Address: 125 N. Market Suite 1000
Wichita, Ks. 67202

Lease Name Davis P Well #1
County Sheridan 127.23

Well Total Depth 3915 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso License Number 6050

Address Chase, Ks.

Company to plug at: Hour: _____ Am _____ Day: 29 Month: mar Year: 19 91

Plugging proposal received from Monte

(company name) Kelso (phone) _____

were: 8 5/8 set at 207 w/150 sks . 4 1/2 set at 3914 w/200 sks. PBDT 3770. Perf 3728 - 385

Order sand and commocommon cement. Pull pipe. Order 225 skls 65/35 poz 8% gel
. 500 lbs. hulls. Allied Cement Co. Hoxie Tank Serviced. Casing free and loose in
hole at 1500. Laid down casing. Ran bailer into fish hole open.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:35 AM Day: 29 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 3645 w/4 sks common cement on sand w/bailer

Shots at 2500, 2000, and 1500. Recovered 1500 of 4 1/2 casing.

Sq 8 5/8 w/225 sks cement blend w/500 lbs. hulls mixed into max psi 1000 lbs.

Close in psi 1000 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

APR 04 1991

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-11-91

INV. NO. 31499

gib.S.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow