

To: 6 062438
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-24
API NUMBER 15- 179-21,007-0000246p
NE, SEC. 16, T 8 S, R 26 W/EK

TECHNICIAN'S PLUGGING REPORT

Operator License # 5663
Operator: Hess Oil Company
Name &
Address 412 E. Douglas #1
Wichita, Kansas 67202

4950 feet from S section line
1320 feet from E section line
Lease Name Taylor Well # 1
County Sheridan 129.02
Well Total Depth 3970 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 211 w/150 sks.

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Mallard JV License Number 4958
Address 2080 E. Kansas, McPherson, Kansas

Company to plug at: Hour: 9:15A.M. Day: 20 Month: June Year: 19 91

Plugging proposal received from James C. Hess
(company name) Mallard J.V. (phone) _____

were: Order 190 sks. 60/40 poznix-6% gel - 3% cal.cl., 1 sk. flo-cel and 8 5/8" plug.
Spot with drill pipe with no less than 36 vis. mud between all plugs, with good
circulation and no fluid loss.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:00A.M. Day: 24 Month: June Year: 19 91

ACTUAL PLUGGING REPORT

- 1st plug @ 2214' w/25 sks.
- 2nd plug @ 1325' w/100 sks. 1 sk. FloGel.
- 3rd plug @ 275' w/40 sks.
- 4th plug @ 40' w/10 sks.

RECEIVED
STATE CORPORATION COMMISSION
7-3-91
JUL 03 1991

Remarks: 15 sks. in Rat Hole - Cemented by: Allied
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, please observe this plugging.)

Signed Gilbert G. Scheck
(TECHNICIAN) E. A. ...

DATE JUL 22 1991

INV. NO. 32327
6-24