

6 030404

15-179-20476-00 00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 9-14-77
CSESW SEC. 17, T. B S, R 26 WE
660 feet from S section line
3300 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145
Operator: Drilling Oil, Inc.
Name & Address Box 1000
Victoria, Kansas
67671

Lease Name Kupar Well 15
County Sheridan Co. 124.93
Well Total Depth 3844 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 178 ✓

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Drilling Oil, Inc. License Number 5145
Address as above

Company to plug at: Hour: PM Day: 27 Month: 3 Year: 19 85

Plugging proposal received from Ivan
(company name) Drilling Oil, Inc. (phone) _____

were: 8 5/8 set @ 178 w/ 150sf cement 4 1/2 set @ 3842 w/ 150sf perf. @ 3615 to 3802. No pipe pulled - ordered 200sf 50/50 poly 6 bag 3% cc 20sf gel. 5sf hulls. Sun Cement. one 4 1/2 w.P. Company water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:PM Day: 27 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Pump down 4 1/2 w/ 50sf hulls 10sf gel 60sf Cement 15sf gel. 90sf cement and 4 1/2" w.P. Pump down backside 4 1/2 - 8 3/8 annulus. w/ 50sf cement. Max Pressure 300^{psi} Shut in 150^{psi} Plugging Complete.

STATE CORPORATION COMMISSION

APR 05 1985
4-5-1985
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired, observe this plugging.)

DATE 4-9-85

INV. NO. 7523

Signed Carl Goodrow
(TECHNICIAN)

4-3-85
JC